



NOTES:

- 1.) ALL EXTERNAL PIPING TO THE TANK IS TO BE SUPPLIED AND INSTALLED BY THE INSTALLATION CONTRACTOR.
- 2.) FOUNDATION PAD MATERIALS AND DESIGN IS DETERMINED BY THE PROJECT ENGINEER AFTER SOIL ANALYSIS IS COMPLETED
- 3.) MATERIALS FOR ANCHORING OF TANK TO THE FOUNDATION PAD IS TO BE SUPPLIED BY OTHERS
- 4.) INCOMING ELECTRICAL POWER AND CONNECTION TO THE CONTROL PANEL IS BY THE ELECTRICAL CONTRACTOR.
- 5.) DUE TO SHIPPING LENGTH LIMITATIONS TANK LENGTH MUST BE FIELD SPLICED AT THE X-X AXIS AND RECONNECTED IN THE FIELD BY WATERTIGHT WELDING. NO SPLICE REQUIRED ON PP-23-ESC AND BELOW

REV.	DATE	ADDED NOTE #5 AND SPLICE MARK DESCRIPTION	JJM
	12/7/05		APP.

PCS Pollution Control Systems, Inc.
 5827 Happy Hollow Ln, Suite 1B
 Milford, Ohio 45150
 (513) 831-1165
 E-mail PolConSys@aol.com

THIS DRAWING CONTAINS INFORMATION THAT IS PROPRIETARY TO POLLUTION CONTROL SYSTEMS AND IS NOT TO BE USED WITHOUT WRITTEN PERMISSION OF POLLUTION CONTROL SYSTEMS, INC.

PREFABRICATED PACKAGE WASTEWATER PLANT			
SCALE: NTS	PROJECT NO.		
DRAWN BY: JJM	DATE: 6/18/98	SHEET	DRAWING NO.
CHECKED BY: JJM	DATE: 6/21/98	1 OF 1	P07-ESC

PLANT MODEL NUMBER	DESIGN FLOW GPD	AERATION TANK VOLUME	CLARIFIER TANK VOLUME	SLUDGE TANK VOLUME	CHLORINE CONTACT TANK-VOL	FLOW EQ. TANK		FLOW EQ. BLOWER		MAIN AIR BLOWER	
						VOLUME	VOLUME	HP	CFM	HP	CFM

OPTIONAL EQUIPMENT/ MATERIALS/TANKAGE

FULL TANK GRATING	ANCHOR BRK'TS	COMMUNITER	U V DISINFECTION
BAR TYPE GRATING	MAGNESIUM ANODES	GRINDER PUMPS	
WELDED HANDRAILS	SCH.40 STL. DROP PIPES	PUMP GUIDE RAILS	NEMA 4X PANEL
BOLTED HANDRAILS	GALVANIZED PIPING	EPOXY PAINT SYSTEM	REMOTE MOUNTED BLOWERS & CONTROLS
HANDRAIL TOEPLATES	STN. STL. DIFFUSERS	DE-CHLORINATION	DOSING TANK
LADDERS/ STAIRWAYS	FROTH SPRAY SYSTEM	GAS CHLORINATION	TERTIARY FILTERS